

DATASHEET

rev. 00 - 24/10/2022

PROAIR PACK CAB GREEN 2L

with plenum in insulated sheet metal

GAD400399 - GAD400400



DESCRIPTION

The pre-assembled systems PROAIR PACK CAB-L are designed to facilitate and speed up the installation of a ducted system. Simply indicate, when ordering, the model of the plenum or alternatively communicate the size of the plenum and specify the code of the chosen PROAIR PACK system.

Il sistema viene fornito completo di centralina "Polaris", cronotermostati e kit by pass meccanico da installare sul plenum (completo di ghiera di fissaggio e contrappeso).

The system is supplied complete with programmable thermostats and dampers (Ø 150 - Ø 200) fixed on the insulated plenum. In order to ensure ease and speed of installation, the PROAIR PACK CAB-L system is completely assembled, configured and tested 100% by qualified personnel.

Wired programmable chrono-thermostats included in the Pack:

- 2 STEALTH 3X timed thermostats white

The PROAIR PACK CAB GREEN 2L system consists of:

- 1 insulated delivery plenum for ducted units (specify plenum code when ordering)
- N° 1 centralina "Polaris" con protocolli precaricati, app, Alexa e Google Home
- 2 motorised dampers pre-wired to system
- 2 STEALTH 3X backlit timed thermostats (white built-in wired)
- 1 mechanical bypass kit to be fastened to plenum (includes fastening ring nut and counterweight)
- 1 50 m cable reel, 4-wire for timed thermostat connection

Customisable on request

Attention! Check with the manufacturer of the indoor ducted unit whether or not it is necessary to use an appropriate interface for the control of the same (mandatory if the communication protocol is not used).

ITEMS

CODE	DESCRIPTION
GAD400399	PROAIR PACK CAB GREEN 2 - WITH 2 CHRONOTERMOSTATSSTEALTH 3X - WITH CONTROL UNIT POLARIS 5X - Ø150 mm
GAD400400	